

KANSAS

4
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20105-00-00

RECEIVED
STATE CORPORATION COMMISSION
FEB 1 1971
CONSERVATION DIVISION
Wichita, Kansas
2-1-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Aspen Resources, Limited and Donald C. Slawson,

Complete Address 710 One-Twenty Building, Wichita, Kansas.

Lease Name Kisling Well No. A-1

Location CNW-SW Sec. 4 Twp. 1 Rge. (E) (W) 34

County Rawlins Total Depth 3020'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Aspen Resources, Limited,

Address 710 One-Twenty Building, Wichita, Kansas. License No.

Operation Completed: Hour 10:30 PM Day 27 Month 1 Year 1971

The above well was plugged as follows:

369'--8 5/8" Surface casing, cement circulated with ---.
Top of Dakota section @ 1875'.

Circulated hole with heavy mud. Pulled DP to 2100' and displaced 100 Sx. cement
thru DP from 2100' to 1775'. Pulled DP to 375' and displaced 25 Sx. cement thru
DP from 375' to 300'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *K. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 2-1-71
INV. NO. 3284-W