

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20029-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Murfin Drilling Company,

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name Ohlson Well No. 1

Location CSW-NW Sec. 3 Twp. 1 Rge. (E) (W) 34

County Rawlins Total Depth 4287

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Above

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 2:00 AM Day 11 Month 8 Year 1968

The Above well was plugged as follows:

283'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1875'.

Circulated hole with heavy mud. Pulled DP to 2100' and displaced 100 Sx. cement thru  
DP from 2100' to 1780'. Pulled DP to 300' and displaced 20 Sx. cement thru DP from  
300' to 240'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

RECEIVED

AUG 14 1968

CONSERVATION DIVISION  
Wichita, Kansas

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 8/14/68

INV. NO. 8281-W

8-14-68