

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC 27 1966  
12-27-66  
CONSERVATION DIVISION  
Wichita, Kansas

7

15-153-30049-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Empire Drilling Company,

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name Souчек Well No. 1

Location CNW-NE Sec. 2 Twp. 1 Rge. (E) (W) 34

County Rawlins Total Depth 4205

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 4:00PM Day 22 Month 12 Year 1966

The Above well was plugged as follows:

188'--8 5/8" Surface pipe, cement circulated with 135 Sx.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.

cement thru DP. Heavy mud to 220', set plug with 1/2 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. D. Dschaw  
Well Plugging Supervisor

DATE 12/27/66

INV. NO. 4525-W