

KANSAS

*Y* STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

15-153-20081-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 30 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
11-30-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name Ohlson Well No. 1

Location CSE-NW Sec. 2 Twp. 1 Rge. (E) (W) 34

County Rawlins Total Depth 4300'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Forbes Casing Pulling Company, Incorporated,

Address Box #211, Great Bend, Kansas. License No. 637

Operation Completed: Hour 7:30 PM Day 23 Month 11 Year 1970

The above well was plugged as follows:

220'--8 5/8" Surface casing, cement circulated.  
4299'--4 1/2" Production casing cemented on bottom with 150 Sx. Plugged back to 4262'.  
Top perforation @ 4096'.

Pushed plug to 4050', sanded back to 4000' and set 3 Sx. cement with dump bailer.

Pulled 4 1/2" casing (1900') and squeezed well initially with 5 sacks hulls and 5 sacks gel and followed with 100 Sx. cement from 2025' to 1700' then 32 sacks gel from 1700' to 250' and followed with 25 Sx. cement from 250' to 175' then 3 sacks gel from 175' 40' and finally 10 Sx. cement from 40' to bottom of cellar. Maximum pump-in pressure-150#. Final shut-in pressure-50#. (Mudding and cementing by Allied Cementing).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *N. L. Nichols*  
Well Plugging Supervisor

DATE 12/1/70  
INV. NO. 2930-W