

40  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

~~15-153-30048-00-00~~  
15-153-05271-00-00

APR 19 1965  
4-19-65  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Empire Drilling Company,

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name Hedke Well No. 1

Location CSE-NW Sec. 1 Twp. 1 Rge. (E) (W) 34

County Rawlins Total Depth 4586

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address:  License No.

Operation Completed: Hour 3:30PM Day 14 Month 4 Year 1965

The Above well was plugged as follows:

219'--8 5/8" Surface pipe, cement circulated with 125 Sx.  
Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx. cement  
thru DP. Heavy mud to 210', set plug with 1/4 sack hulls and displaced 20 Sx.  
cement thru DP. Heavy mud to 40', set plug with 1/2 sack hulls and 10 Sx.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. [Signature]  
Well Plugging Supervisor

DATE 4/19/65  
INV. NO. 995-W