

INJ Kislina "A" -1

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-153-05219-0001
LEASE NAME TEXACO CAHOJ UNIT

TYPE OR PRINT
E16643
SPOT SE SW

WELL NUMBER 2
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

660 Ft. from S Section Line
3300 Ft. from E Section Line

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 4 TWP. 1S RGE. 34W (E) or (W)
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY RAWLINS
PHONE # () 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 4/12/60
Character of Well inj (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 2/22/02
Plugging Completed 2/22/02

The plugging proposal was approved on 2/22/02 (date)
by Rich Williams w/KCC Hays, KS. (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? yes
Producing Formation _____ Depth to Top 4004 Bottom 4198 TD 4334' Show
depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	367	8 5/8	367	0
		production	4334	5 1/2		

RECEIVED
MAR 13 2002
KCC WICHITA

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged well as follows: Hooked up to 1/2" csg. Pumped 285 sxs 60/40 poz. 10% gel & 500# hulls. Max. Press 400# ISIP 100#. Hooked up to 8 5/8" csg. Pumped 70 sxs. 60/40 poz. 10% gel. max press. 300#. OSO 100#/ Checked 5 1/2" csg & found top of cmt @100'. Witnessed and approved by Rich Williams w/KCC Hayes, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address
250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK .SS.


Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 25 th day of Feb 2002

Notary Public - Barbara J. Dodson

My Commission Expires: 12/16/03 Form CP-4 Revised 05-88



OR

SWIFT SERVICES, INC.

PO BOX 466

NESS CITY, 67560-0466

Invoice

DATE	INVOICE #
2/22/02	4294

BILL TO
Murfin Drilling Co. Inc. PO Box 277 Logan, KS 67646

TERMS	Well No.	Lease	County	Contractor	Well Type	Well Category	Operator	Job Purpose
Net 30	2	Texaco-Cahoj	Rawlins			Abandoned	Lenny	PTA

PRICE REFERE...	DESCRIPTION	QTY	UNIT PRICE	AMOUNT
575W	Milage	110	2.50	275.00T
576W-P	Pump Charge	1	500.00	500.00T
329	Swift Ultra Light 60/40 Pozmix (10% gel)	360	5.85	2,106.00T
275	Cotton Seed Hulls	5	22.00	110.00T
581W	Service Charge Cement	360	1.00	360.00T
583W	Drayage	1,278.08	0.75	958.56T
	Subtotal			4,309.56
	Sales Tax		4.90%	211.17

USED FOR PIA - 36
 APPROVED ST BK

RECEIVED
 MAR 13 2002
 FILE COPY
 KCC WICHITA

Thank you for your business.	Total	\$4,520.73
------------------------------	-------	------------



CHARGE TO: Murphy Dry Co.
 ADDRESS: _____
 CITY, STATE, ZIP CODE: Colby 16

RECEIVED
 MAR 13 2002
 KCC WICHITA

TICKET No 4294

PAGE 1 OF 1

SERVICE LOCATIONS 1. <u>Ness City</u>	WELL/PROJECT NO. <u>2</u>	LEASE <u>Texaco-Cahoj</u>	COUNTY/PARISH <u>Rawlins</u>	STATE <u>Ks</u>	CITY	DATE <u>2-22-02</u>	OWNER <u>Same</u>
2.	TICKET TYPE <input checked="" type="checkbox"/> SERVICE <input type="checkbox"/> SALES	CONTRACTOR	RIG NAME/NO.	SHIPPED VIA <u>105</u>	DELIVERED TO <u>N.W. Atwood</u>	ORDER NO.	
3.	WELL TYPE	WELL CATEGORY <u>Abandoned</u>	JOB PURPOSE <u>P.T.A</u>	WELL PERMIT NO.	WELL LOCATION		
4. REFERRAL LOCATION	INVOICE INSTRUCTIONS						

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		UM		UNIT PRICE	AMOUNT
		LOC	ACCT	DF							
575		1			MILEAGE <u>105</u>	110	m			2.50	275.00
576		1			Pump charge	1	SA				500.00
329					60/40 P02 10% Sol	360	SKS			5.85	2106.00
275					Hulls	5	SKS			22.00	110.00
581					Bulk Service Charge	360				1.00	360.00
583					Drayage	1278	OS	T.M.		75	958.56

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY,** and **LIMITED WARRANTY** provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

x [Signature]
 DATE SIGNED: 2-22-02 TIME SIGNED: 1000
 A.M. P.M.

REMIT PAYMENT TO:
 SWIFT SERVICES, INC.
 P.O. BOX 466
 NESS CITY, KS 67560
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?				4309.56
WE UNDERSTOOD AND MET YOUR NEEDS?				
OUR SERVICE WAS PERFORMED WITHOUT DELAY?				
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				TAX
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO				211.17
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND				TOTAL
				4520.73

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR: [Signature] APPROVAL: _____

Thank You!

JOB LOG

SWIFT Services, Inc.

DATE 2-22-02 PAGE NO. 1

CUSTOMER *M. W. G. in* WELL NO. *2* LEASE *Texaco calroy* JOB TYPE *P.T.A.* TICKET NO. *4294*

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	<i>09 45</i>							<i>on loc Pubs 4004 - 4198</i>
								<i>Hookup to 5 1/2 csg TO 4170+-</i>
								<i>Pump 285 SKS 60/40 10% gpt + 500 # hulls</i>
								<i>max PST 400</i>
								<i>shut down PST to 0 5 min</i>
								<i>Hookup & Pump 70 SKS 60/40 10% col down 8 5/8</i>
								<i>max PST 300</i>
								<i>shut in 8 5/8 w/ 100 PST</i>
								<i>Pump 5 SKS Down 5 1/2 100 PST</i>
								<i>shut in at 100 PST</i>
	<i>11 30</i>							<i>Job Complete</i>
								<i>will check later to see if well needs topped off</i>
								<i>Checked 1 hr</i>
								<i>Later TOC @ 5 1/2 290 SKS cmt</i>
								<i>100' 500 # hulls</i>
								<i>8 5/8 70 SKS cmt</i>

RECEIVED
 MAR 13 2002
 KCC WICHITA