


15-153-05275-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rawlins County, Sec. 4 Twp. 1S Rge. 34W (E) (W)

Location as "NE/CNW%SW%" or footage from lines C SE NE

Lease Owner Imperial Oil of Kansas, Inc.

Lease Name Kisling Well No. 1

Office Address 780 Fourth National Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed December 19, 1960

Application for plugging filed February 3, 1961

Application for plugging approved February 5, 1961

Plugging commenced February 6, 1961

Plugging completed February 10, 1961

Reason for abandonment of well or producing formation Commercial quantities of oil depleted.

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. A. D. Fabricius

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4260' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PBT IN	PULLED OUT
				8-5/8"	243'	Not pulled
				4-1/2"	4260'	

RECEIVED
STATE CORPORATION COMMISSION
MARCH 1961
CONSERVATION DIVISION
Wichita, Kansas

3-6-61

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved tools on location. Unloaded. Raised mast. Checked hole. Cleaned cellar. Filled back with sand from 4260' to 4140' (120'). Mixed and run 3 sacks cement with dump bailer. Finished cleaning cellar. Took tension on pipe. Worked and shot pipe. Shots at 2524' - 2308' - 2091' - 1996' - 1903' - 1809' worked pipe free and pulled 40 jts. Pulled 17 jts. Mudded hole and bailed fluid. Set 10' rock bridge at 240'. Mixed and run 25 sacks cement with dump bailer. Mudded hole to 40'. Mixed and run 10 sacks cement on rock bridge to complete plugging.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Company

Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

R. L. Bacon (employee of ~~owner~~ operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: R. L. Bacon V-P

780 Fourth National Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of February 1961

My commission expires October 12, 1964

Cecilia C. Klug
Cecilia C. Klug Notary Public.



DRILLER'S LOG

15-153-05275-00-00

Imperial Oil of Kansas, Inc.
780 Fourth National Building
Wichita 2, Kansas

Kisling No. 1
C SE NE Sec. 4-1-34W
Rawlins County, Kansas

Total Depth: 4260

Elevation: 3067 K.B.
Production:

Commenced: 12-8-60 Completed: 12-19-60

Contractor: Imperial Oil of Kansas, Inc.
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 243 with 150 sax cement.
Set 4-1/2" Production Pipe at 4260 with 150 sax cement.

Figures indicate bottom of formations:		<u>TOPS</u> (Elec. Log)
Surface Sand & Shells	160'	Stone Corral 2919 (7 148)
Sand & Shells	243'	Anhydrite (Sple Top)
Sand & Shale	975'	Topeka 3770 (- 703)
Shale & Shells	2735'	Oread 3859 (- 792)
Shale	2919'	Heebner 3919 (- 852)
Anhydrite	3050'	Lansing 3972 (- 905)
Shale	3800'	B/Kansas City 4244 (-1177)
Shale & Lime	4260'	Total Depth 4261 (-1194)
Rotary Total Depth	4260'	

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By Raymond L. Bacon
Raymond L. Bacon

Subscribed and sworn to before me this 27th day of December, 1960.

My Commission Expires:

October 12, 1964

RECEIVED
STATE CORPORATION COMMISSION

MAR 6 1961

3-6-61
CONSERVATION DIVISION
Wichita, Kansas

Cecilia C. Klug
Cecilia C. Klug, Notary Public