

Orig - State Corp. Comm.

Copy - B. A. Conner - 357 FPB

Copy - Mary Crump - Okla. City

Copy - Well File

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

15-153-20252-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Rawlins SEC. 2 TWP. 1 RGE. 34 E/W
Location as in quarters or footage from lines:
660' FWL & 66' FSL SW/4

Lease Owner Phillips Petroleum Company
Lease Name Chleborad-A Well No. 6
Office Address Box 287, Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed April 30, 1976
Application for plugging filed November 1, 1982
Plugging commenced February 10, 1983
Plugging completed March 9, 1983
Reason for abandonment of well or producing formation Uneconomical

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow

Producing formation LKC Depth to top 4128 bottom 4224 T.D. PB 4312

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface	Water	0'	329'	8 5/8"	318.76'	-0-
Production	Oil & Water	0'	4346'	5 1/2"	4337.66'	1324'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. MIRU Kelso Csg. Pullers & spot 5 sx cmt on bottom w/bailer. Sand back to 4200'. Spot 5 sx cmt on top of sand. Pulled stretch & shot csg @ 3020', 2527', 2016', 1818', 1621', 1423' 1324' - came loose. Pulled & ID 40 jts 5 1/2" csg. RDMO Kelso. On 3-4-83. Conn Hallib to 8 5/8" csg. Pmp 100 sx 50-50 Pozmix w/6% gel & 2 sx hulls; 38 sx gel, 35 sx 50-50 Poz w/6% gel, 8 5/8" wiper plug, 35 sx 50-50 Poz w/6% gel @ 4 BPM. Max press 300 psi. ISIP 300#. Release Hallib. Weld plate on 8 5/8" csg. Well P&A 3-4-83

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pullers, Inc.
Chase, Kansas

STATE OF Kansas COUNTY OF Barton, ss.

C. D. Dohrer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. D. Dohrer Area Mgr.
Box 287, Great Bend, Kansas 67530
(Address)



SUBSCRIBED AND SWORN TO before me this 9th day of March, 19 83

Velma L. Mog Notary Public.

My Commission expires: February 15, 1984

RECEIVED
STATE CORPORATION COMMISSION
3-10-83
MAR 10 1983
CONSERVATION DIVISION
Wichita, Kansas

15-153-20252-00-00

Phillips Petroleum Company

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No.

6

Lease Name

Chleborad "A"

Oil

S 2 T 1 S R 34 E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface hole	0'	330'		
Shale and shells	330'	2298'		
Shale and shells	2298'	2677'		
Shale	2677'	2684'		
Anhydrite	2684'	2711'		
shale and lime	2711'	3150'		
Lime and shale	3150'	3625'		
Shale and lime	3625'	3806'		
Lime and shale	3806'	3958'		
Lime	3958'	4330'		
Lime and shale	4330'	4350'		
RTD	4350'			
Plug back TD	4312'			

RECEIVED
 STATE CORPORATION COMMISSION
 11-2-82
 NOV 2 1982
 CONSERVATION DIVISION
 Wichita Kansas

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

C. S. Sohar
 Signature

Area Superintendent

Title

April 29, 1976

Date