

Original - State Corporation Commission  
 Copy - Ruby Ewing - 343 FPB - Bartlesville  
 Copy - Oklahoma City Office  
 Copy - Well File

FORM CP-4


15-153-20120-00-00

STATE OF KANSAS  
 STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit  
 Mail or Deliver Report to  
 Conservation Division  
 State Corporation Comm.  
 245 North Water  
 Wichita, KS 67202

Rawlins County, Sec. 2 Twp. 1S Rge. 34 E/W  
 Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
 C SW SW  
 Lease Owner Phillips Petroleum Company  
 Lease Name Chleborad - A Well No. 2  
 Office Address Box 287, Great Bend, Kansas 67530  
 Character of Well (Completed as Oil, Gas or Dry Hole)  
 Oil  
 Date Well completed July 2 1971  
 Application for plugging filed September 6 1979  
 Application for plugging approved September 7 1979  
 Plugging commenced September 15 1979  
 Plugging completed September 21 1979  
 Reason for abandonment of well or producing formation  
 Casing leak  
 If a producing well is abandoned, date of last production  
 July 1 1977



Locate well correctly on above  
 Section Plot

Name of Conservation Agent who supervised plugging of this well Gilbert Balthozer  
 Producing formation LKC Depth to top 3989 Bottom 4210 Total Depth of Well 4240  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	Water	0'	280'	8 5/8"	280'	0'
Production	Oil & Water	0'	4239'	5 1/2"	4239'	2218'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set. On 9-15-79 MIRU Kelso Csg Pullers. Dug out cellar, ran bailer, set down @ 2977'. Pulled 19" stretch on 5 1/2" pipe. Pulled 21" stretch. Shot pipe @ 2703', 2596', 2465', 2208' - pipe came loose. Pulled pipe & pmpd 9#/gal gel mud. Pulled 2 jts 5 1/2" & Hallib pmpd 80 sx cement, 3 sx hulls, 15 sx gel & a plug. Circ after 15 Bbls in. Pld 45 jts 5 1/2" csg (total rec 2217.80'). Started 8 5/8" plug - pmpd 80 sx cement @ 150# - SI pres 100#. RDMO Kelso Csg Pullers. Welded steel plate on 8 5/8" csg. Well P&A 9-21-79

RECEIVED

STATE CORPORATION COMMISSION

(If additional description is necessary, use back of this sheet)


Name of Plugging Contractor Kelso Casing Pullers  
 Box 176, Chase, Kansas 67524  
 SEP 25 1979  
 9-25-79  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF Kansas COUNTY OF Barton ss.

C. D. Dohrer (employee of owner) or (owner or operator) of the above-described well being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. D. Dohrer  
 C. D. Dohrer, District Superintendent  
 Box 287, Great Bend, Kansas 67530  
 (Address)

Subscribed and sworn to before me this 24th day of September 19 79



Velma L. Spanier  
 Notary Public.

My commission expires March 18, 1980

# WELL LOG

15-153-20120-00-00

COMPANY Thos. H. Allan

SEC. 2 T. 1S R. 34W  
LOC. C SW SW

FARM Chleborad NO. 2

RIG. NO. 8

COUNTRY Rawlins  
KANSAS

TOTAL DEPTH 4240'


COMM. 6-24-71

COMP. 7-2-71

SHOT OR TREATED

CONTRACTOR Murfin Drilling Company

ISSUED



CASING

20	10	
15	8	5/8" @ 280' w/225 SXS
12	6	
13	5	1/2" @ 4239' w/125 SXS

ELEVATION 3079' K.B.

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

200	Clay & Sand
280	Blue Shale
1045	Shale
2665	Shale & Sand
2942	Shale
2980	Anhydrite
3200	Shale
4240	Lime & Shale

RECEIVED  
STATE CORPORATION COMMISSION

MAY 15 1979

CONSERVATION DIVISION  
Wichita, Kansas

5-15-79

State of Kansas

County of Sedgwick

I, James R. Daniels of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Chleborad #2 well.

Subscribed and sworn to before me this 13th day of July 19 71

February 7, 1975

Wilma V. Brokes  
WILMA V. BROKES, PUBLIC

