



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

15-153-05267-00-00

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 28 1965
05-28-1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Darrell Kelso of Knight Casing Pulling Co. has this date requested permission to plug the following described well:
Bovaird Supply Co.,
Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Bovaird Supply Company,

Complete Address: 414 Union Center, Wichita, Kansas.

Lease Name: Simlinger Well No. 2

Location: App. CNE-NW Sec. 30 Twp. 1 Rge. (E)(W) 32

County Rawlins Total Depth 4326 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kelso was instructed to plug the well as follows:

301'-- 8 5/8" Surface pipe, cement circulated.
4326'--5 1/2" Production casing cemented with 150 Sz. Top perforations from 4203' to 4206'.

Sand well back to 4190' and set 5 Sz. cement with dump bailer.
Pull 5 1/2", bail hole to 600', set rock bridge and fill 100' of hole from 600' to 500' with Redi-Mix cement. Fill hole with mud from 500' to 300', set rock bridge @ 300' and fill hole from 300' to bottom of cellar with Redi-Mix cement.

Very truly yours,

H. L. Nichols
Conservation Division Agent