



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-153-20118-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1977
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Art Hunt of Rains & Williamson Oil Co., has this date requested permission to plug the following described well:

Mr. Hunt guarantees payment of the plugging fee.

Operator's full Name: Adair Oil Company,

Complete Address: Box #7011, Wichita, Kansas.

Lease Name: Summinger Well No. 1

Location: App: NW-NW Sec. 30 Twp. 1 Rge. (E)(W) 32

County: Rawlins Total Depth 4275' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hunt was instructed to plug the well as follows:

322'--8 5/8" Surface casing, cement circulated with 275 Sx.
Top of Dakota section @ 1900'.

Circulate hole with heavy mud. Pull DP to 2125' and displace 100 Sx.
cement thru DP. Pull DP to 330' and displace 30 Sx. cement thru DP.
Pull DP, set bridge @ 80' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent