

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-153-20,766-00-00 (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Thunderbird Drilling, Inc. OPERATOR'S LICENSE NO. 5131

ADDRESS P.O. Box 780407, Wichita, KS 67278 PHONE # (316) 685-1441

LEASE (FARM) Michel WELL NO. 1 WELL LOCATION C SW SW COUNTY Rawlins

SEC. 31 TWP. 1S RGE. 32 (E) or (W) TOTAL DEPTH 4290' PLUG BACK TD _____

Check One:

OIL WELL ___ GAS WELL ___ D & A X SWD or INJ WELL ___ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 333' CEMENTED WITH 60-40 pozmix SACKS 230

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS _____

PERFORATED AT _____

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 2875' w/25 sx; 2nd plug @ 2195' w/100 sx; 3rd plug @ 385' w/40 sx; 4th plug @ 40' w/wiper plug w/10 sx; Rathole 15 sx; 60-40 pozmix 6% gel 1/4# Flocel.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? no
(If not explain.) Sent to Operator to complete

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 12-18-90 1:00 a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Maley PHONE # (913) 674-5768 01-11-1991

ADDRESS 216 E. McFarland, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack K. Wharton
(Operator or Agent)

DATE: January 10, 1991