



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-153-20105-00-00

RECEIVED
STATE CORPORATION COMMISSION
FEB 1 1971
CONSERVATION DIVISION
Wichita, Kansas

2-1-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Earl Morgan of Aspen Resources, Limited has this

date requested permission to plug the following described well:

Mr. Morgan guarantees payment of the plugging fee.

Operator's full Name: Aspen Resources, Limited and Donald C. Slawson,

Complete Address: 710 One-Twenty Building, Wichita, Kansas.

Lease Name: Kisling Well No. A-1

Location: CNW-SW Sec. 4 Twp. 1 Rge. (E)(W) 34

County: Rawlins Total Depth 3020' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Morgan was instructed to plug the well as follows:

369'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 1875'.

Circulated hole with heavy mud. Pull DP to 2100' and displace 100 Sx.
cement thru DP. Pull DP to 375' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent