



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Don Favinger of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Favinger guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company,

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name: Ohlson Well No. 1

Location: CSW-NW Sec. 3 Twp. 1 Rge. (E)(W) 34

County: Rawlins Total Depth 4287 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Favinger was instructed to plug the well as follows:

283'---8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1875'.

Circulate hole with heavy mud. Pull DP to 2100' and displace 100 Sx.
cement thru DP. Pull DP to 300' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

RECEIVED

STATE CORPORATION COMMISSION

AUG 14 1968

CONSERVATION DIVISION
Wichita, Kansas

8-14-68

Very truly yours,

Conservation Division Agent