



15-153-20081-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 30 1970
CONSERVATION DIVISION
Wichita, Kansas
11-30-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Forbes Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Incorporated,

Complete Address: 905 Century Plaza, Wichita, Kansas.

Lease Name: Ohlson Well No. 1

Location: CSE-NW Sec. 2 Twp. 1 Rge. (E)(W) 34

County: Rawlins Total Depth 4300' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pulley was instructed to plug the well as follows:

220'--8 5/8" Surface casing, cement circulated.

4299'--4 1/2" Production casing cemented on bottom with 150 Sx. Plugged back to 4262'. Top perforation @ 4096'.

Push plug to 4050', sand to 4000' and set 3 Sx. cement with dump bailer.
Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 40 sacks gel and 135 Sx. cement staged.

Very truly yours,

M. L. Nichols
Conservation Division Agent