

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-05267-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAY 28 1965
05-28-1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Bovaird Supply Company,

Complete Address: 414 Union Center, Wichita, Kansas.

Lease Name Simlinger Well No. 2

Location App. CNE-NW Sec. 30 Twp. 1 Rge. (E) (W) 32

County Rawlins Total Depth 4326

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company,

Address: Box # 405, Chase, Kansas. License No. 436

Operation Completed: Hour 8:00PM Day 25 Month 5 Year 1965

The Above well was plugged as follows:

301'--8 5/8" Surface pipe, cement circulated.
4326'--5 1/2" Production casing cemented with 150 Sx. Top perforations from
4203' to 4206'.

Sanded well back to 4190' and set 5 Sx. cement with dump bailer. Pulled
5 1/2". Bailed hole to 600', set rock bridge and filled hole from 600' to
500' with Redi-Mix cement. Filled hole with mud from 500' to 300', set
rock bridge @ 300' and filled Hole from 300' to bottom of cellar with
Redi-Mix cement. (Used 5 1/2 yards Redi-Mix)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Dichel
Well Plugging Supervisor

DATE 5/28/65

INV. NO. 1231-W