

KANSAS

Form CP-3
Rev. 6-4-68

R

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
06-10-1971
JUN 10 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-153-~~2018~~-00-00
20118

Operator's Full Name Adair Oil Company,

Complete Address Box #7011, Wichita, Kansas.

Lease Name Swimminger Well No. 1

Location App: NW-NW Sec. 30 Twp. 1 Rge. (E) (W) 32

County Rawlins Total Depth 4275'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Rains & Williamson Oil Company, Incorporated,

Address 1425 Wichita Plaza, Wichita, Ks. License No.

Operation Completed: Hour 6:00 AM Day 2 Month 6 Year 1971

The above well was plugged as follows:

322'--8 5/8" Surface casing, cement circulated with 275 Sx.
Top of Dakota section @ 1900'.

Circulated hole with heavy mud. Pulled DP to 2125' and displaced 100 Sx. cement thru
DP from 2125' to 1800'. Pulled DP to 330' and displaced 30 Sx. cement thru DP from
330' to 240'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 6-10-71
INV. NO. 3840-W