

**Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

073-19380-0000

Lease Operator: Rig 6 Drilling, Inc.  
 Address: P.O.Box 227, Iola, KS 66749  
 Phone: (620) 365-6294 Operator License #: 30567  
 Type of Well: Oil Docket #: \_\_\_\_\_  
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
 The plugging proposal was approved on: 11/2/04 (written) 3/22/04 (oral) (Date)  
 by: 11/2 Mike Heffern, 3/22 Ron Rowe (KCC District Agent's Name)  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (if needed attach another sheet)  
Bartlesville Depth to Top: 1930 Bottom: 1938 T.D. 1980  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-N/A  
 Lease Name: Greenwood  
 Well Number: 7  
 Spot Location (QQQQ): NE NE  
SWW - NAW - S/W - 1/4  
3300 2352 Feet from  North /  South Section Line  
4320 3009' Feet from  East /  West Section Line  
 Sec. 19 Twp. 22 S. R. 11  East  West  
 County: Greenwood  
 Date Well Completed: N/A  
 Plugging Commenced: 3/23/04  
 Plugging Completed: 3/25/04

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
<u>Bartlesville</u>	<u>oil/13 ft</u>	<u>0</u>	<u>1980</u>	<u>4 1/2</u>	<u>1950</u>	<u>none</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

3/23/04 Hurricane Well Serv ran in tubing to t.d. & pump 10 sx portland, pull out tubing. 3/24/04 Precision wireline perforate @ 10 1050'(douglass) and 200'. Hurricane ran tubing in & pumped 10 sx portland @ 1050. Pulled tubing to 200' & pumped 27 sx portland, well equalizing up annulus. 3/25/04 pumped 11 sx portland (fill fall-back both sides 4 1/2) . 2 % gel use in all mixes

Name of Plugging Contractor: Rig 6 Drilling, Inc License #: 30567  
 Address: P O Box 227, Iola, Ks 66749  
 Name of Party Responsible for Plugging Fees: Same  
 State of ks County, allen, ss.

Raymond K Sifers, Pres Rig 6 Drilling (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]  
 (Address) P.O. Box 227 Iola, KS

SUBSCRIBED and SWORN TO before me this 8 day of April, 2004  
Eleanor Ruth Spangler My Commission Expires: Nov 3, 2006  
 Notary Public

RECEIVED  
 APR 22 2004  
 04-22-04  
 KCC WICHITA

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Signature]