

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Falcon Exploration, Inc.
Address: 155 N. Market, Suite 1020, Wichita, KS 67202
Phone: (316) 262-1378 Operator License #: 5316
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: Feb. 12, 2004 (Date)
by: David P. Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 4356 Bottom: 4363 T.D. 4363
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-135-23467-06-00
Lease Name: Adam
Well Number: #1
Spot Location (QQQQ): NE - E - SE - NW
3510 Feet from North / South Section Line
3090 Feet from East / West Section Line
Sec. 14 Twp. 20 S. R. 22 East West
County: Ness
Date Well Completed: 07/12/90
Plugging Commenced: 03/18/04
Plugging Completed: 03/19/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
<u>Mississippi / Surf</u>	<u>Oil & Water</u>	<u>4354</u>	<u>4363</u>	<u>8 5/8</u>	<u>651</u>	<u>0</u>
<u>Prod</u>				<u>5 1/2</u>	<u>4354</u>	<u>appr. 1258 (31jts)</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Went in with dump bailer, tagged bottom at 4350', dumped sand, went in with bailer again and tagged sand at 4250', dump 4 sx cement, let set overnight; loggers backed off casing at 1300', pulled 31 jts of 5 1/2 casing; 1st plug at 1250' with 50 sx 60/40 6% gel cement; 2nd plug at 700' with 80 sx 60/40 6% gel cement; 3rd plug at 250' with 40 sx 60/40 6% gel cement; 4th plug at 40' with 10 sx 60/40 6% gel cement

Name of Plugging Contractor: Plains, Inc. License #: 4072
Address: P.O. Box 346, Ness City, KS 67560
Name of Party Responsible for Plugging Fees: Falcon Exploration, Inc.
State of Kansas County, Sedgwick, ss.

RECEIVED
MAY 05 2004
KCC WICHITA

Micheal S. Mitchell (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Falcon Exploration, Inc, 155 N. Market, Ste 1020, Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 3rd day of May, 20 04

Rosann M Schippers My Commission Expires: 9/28/07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



