

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 130 S. Market, Room 2078  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-62-3-117

15-009-15453-00-00

API NUMBER \_\_\_\_\_

LEASE NAME Eveleigh B

WELL NUMBER ① 7

330 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 5 TWP. 18 SRGE. 12 (E) or (W) (W)

COUNTY Barton

Date Well Completed 2/19/61

Plugging Commenced 4/15/04

Plugging Completed 4/15/04

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Nadel and Gussman, L.L.C.

ADDRESS 3200 First Place Tower, Tulsa, OK 74103

PHONE# (918) 583-3333 OPERATORS LICENSE NO. 32638

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4/15/04 2/19/04 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3344 Bottom 3348 T.D. 3348

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Depleted	0	250	8-5/8	250	None
		0	3345	5-1/2	3345	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Perforated 4 holes 1304 to 1305 and 4 holes 725 to 726. Pumped 20 sks Gel and 35 sks 60/40 10% gel w/200# hulls @ 3400'. Pulled tubing to 1300' and pumped 100 sks 60/40 10% gel w/250# hulls and circulated to surface. Pulled tubing. Hooked to 5-1/2" casing and pumped in 50 sks to 400#. Shut in @ 250#. Hooked to annulus and pumped in 50 sks @ 700#. Shut in 500#.

Name of Plugging Contractor Allied Cementing License No. N/A 99996

Address P.O. Box 31, Russell, KS 67605

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Nadel and Gussman, L.L.C.

STATE OF Oklahoma COUNTY OF Tulsa, ss.

M.R. Taylor, Manager of Production (Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) M.R. Taylor

(Address) 15 E. 5th St., Suite 3200, Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 29 day of April, 19 2004

Kathy Carr  
 Notary Public

My Commission Expires: 8-1-07

RECEIVED  
 MAY 03 2004  
 KCC WICHITA

# ALLIED CEMENTING CO., INC.

18287

Federal Tax I.D. # ~~48-8727860~~

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

At Bond

DATE <u>4.15.04</u>	SEC. <u>5</u>	TWP. <u>18</u>	RANGE <u>12</u>	CALLED OUT <u>8:00AM</u>	ON LOCATION <u>10:15AM</u>	JOB START <u>11:30AM</u>	JOB FINISH <u>2:30 PM</u>
LEASE <u>Eveligh</u>	WELL # <u>B-2</u>	LOCATION <u>Adwing 1W, 1S, E/winter</u>			COUNTY <u>Butler</u>	STATE <u>Kn</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR \_\_\_\_\_

TYPE OF JOB Plug to Abandon

HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_

CASING SIZE 5 1/2" DEPTH \_\_\_\_\_

TUBING SIZE 2 1/2" DEPTH 3400'

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX 700\* MINIMUM \_\_\_\_\_

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT \_\_\_\_\_

OWNER Some

CEMENT

AMOUNT ORDERED 2500lb 69/40 1080lb

200lb net

700\* Hubs used 2350lb cement

used 450\* Hubs

COMMON	<u>1 1/4"</u>	@	<u>7.15</u>	<u>1078.15</u>
POZMIX	<u>74 lb</u>	@	<u>4.00</u>	<u>296.00</u>
GEL	<u>40 net</u>	@	<u>11.00</u>	<u>440.00</u>
CHLORIDE		@		
ASC		@		
<u>Hubs</u>	<u>450*</u>	@	<u>20.00</u>	<u>9000.00</u>
		@		
		@		
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>277 lb</u>	@	<u>1.25</u>	<u>346.25</u>
MILEAGE	<u>277 44 05</u>	@	<u>15</u>	<u>4155.00</u>
TOTAL				<u>2522.65</u>

**EQUIPMENT**

PUMP TRUCK CEMENTER Tom D

# 181 HELPER Bob B

BULK TRUCK

# 344 DRIVER Don Dinitz

BULK TRUCK

# \_\_\_\_\_ DRIVER \_\_\_\_\_

**REMARKS:**

Mixed - 200lb net - 350lb 69/40 1080lb  
 1/200\* Hubs @ 3400'. Pulled tubing up  
 to 1300'. Mixed 1000lb 69/40 1080lb  
 1/250\* Hubs + circulated to surface.  
 Pulled tubing. Handed to 55' via. Mixed  
 500lb + handed to 400\* shot in 250\*  
 Handed to hoppers. Mixed 500lb + handed  
 to 700\* shot in = 500\*.

*[Signature]*

**SERVICE**

DEPTH OF JOB 3400'

PUMP TRUCK CHARGE \_\_\_\_\_ 630.00

EXTRA FOOTAGE \_\_\_\_\_ @ \_\_\_\_\_

MILEAGE 15 @ 4.00 60.00

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

TOTAL 690.00

**PLUG & FLOAT EQUIPMENT**

MANIFOLD \_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

TOTAL \_\_\_\_\_

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment  
 and furnish cementer and helper to assist owner or  
 contractor to do work as is listed. The above work was  
 done to satisfaction and supervision of owner agent or  
 contractor. I have read & understand the "TERMS AND  
 CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE X [Signature]

X Art Polo  
 PRINTED NAME

RECEIVED

MAY 03 2004

KCC WICHITA