

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Falcon Exploration, Inc.  
Address: 155 N. Market, Ste 1020; Wichita, KS 67202  
Phone: (316) 262-1378 Operator License #: 5316  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: February 12, 2004 (Date)  
by: David P. Williams (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Mississippi Depth to Top: 4393 Bottom: 4600 T.D. 4962  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-135-23174~00-00  
Lease Name: Maier  
Well Number: #3  
Spot Location (QQQQ): C - NE - NE - \_\_\_\_\_  
4620 Feet from  North /  South Section Line  
660 Feet from  East /  West Section Line  
Sec. 14 Twp. 20 S. R. 22  East  West  
County: Ness  
Date Well Completed: 11/23/87  
Plugging Commenced: 03/19/04  
Plugging Completed: 03/22/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
<u>Mississippi / Surf</u>	<u>Oil &amp; Water</u>	<u>4394</u>	<u>4397</u>	<u>8 5/8</u>	<u>620</u>	<u>0</u>
<u>Prod</u>			<u>4750</u>	<u>5 1/2</u>	<u>4750</u>	<u>0</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

bullhead 5 1/2" casing, mix 30 sx 60/40 6% gel with 200 lbs hulls, followed with 11 sx gel mixed with 24 bbl water; press with 2000#; pumped 15 sx 60/40 6% gel into annulus, press with 500#; trip in hole with 33 jts tubing, circ to surface with 80 sx 60/40 6% gel cement; pull tubing and top off with 10 sx 60/40 6% gel cement; hole stayed full


Name of Plugging Contractor: Plains, Inc. License #: 4072 **RECEIVED**  
Address: P. O. Box 346; Ness City, KS 67560 **MAY 05 2004**  
Name of Party Responsible for Plugging Fees: Falcon Exploration, Inc. **KCC WICHITA**  
State of Kansas County, Sedgwick, ss.

Micheal S. Mitchell  
(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) Falcon Exploration, Inc.; 155 N. Market, Ste 1020; Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 3rd day of May, 20 04  
Rosann M Schippers My Commission Expires: 9/28/07  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



# ALLIED CEMENTING CO., INC. 18276

Federal Tax I.D.# ~~00-0727000~~

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT: Mass City

DATE <u>3-22-04</u>	SEC. <u>14</u>	TWP. <u>203</u>	RANGE <u>22W</u>	CALLED OUT <u>8:30 am</u>	ON LOCATION <u>9:30 am</u>	JOB START <u>9:45 am</u>	JOB FINISH <u>11:00 am</u>
LEASE <u>MAIER</u>		WELL #	LOCATION <u>Bazine - 8 south - 3/4 west</u>	COUNTY <u>Mass</u>	STATE <u>KS</u>		
OLD OR NEW (Circle one)			<u>South into</u>				

CONTRACTOR Plains

TYPE OF JOB Top off 299 - old hole

HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_

CASING SIZE .52 DEPTH 1000'

TUBING SIZE 2" DEPTH 1000'

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT \_\_\_\_\_

OWNER Falcon

CEMENT AMOUNT ORDERED 200 sy 10/10 6.90 gel  
Used 90 sy cement

COMMON	<u>54 "A"</u>	@	<u>7.15</u>	<u>386.10</u>
POZMIX	<u>36</u>	@	<u>3.80</u>	<u>136.80</u>
GEL	<u>5</u>	@	<u>10.00</u>	<u>50.00</u>
CHLORIDE		@		
ASC		@		
		@		
		@		
		@		
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>210</u>	@	<u>1.15</u>	<u>241.50</u>
MILEAGE	<u>24 x 210 x .05</u>			<u>252.00</u>
TOTAL				<u>1066.40</u>

**EQUIPMENT**

PUMP TRUCK CEMENTER Jack

# 224 HELPER Jim

BULK TRUCK

# 344 DRIVER Dan

BULK TRUCK

# \_\_\_\_\_ DRIVER \_\_\_\_\_

**REMARKS:**

Run tubing down to 1000' - size 2" - surface with 80 sy cement - pull tubing & top off with 10 sy cement - hole stopped full

Thanks

**SERVICE**

DEPTH OF JOB				
PUMP TRUCK CHARGE				<u>475.00</u>
EXTRA FOOTAGE		@		
MILEAGE	<u>24</u>	@	<u>3.50</u>	<u>84.00</u>
		@		
		@		
		@		

CHARGE TO: Falcon Exploration

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

RECEIVED

TOTAL 559.00

MAY 05 2004

KCC WICHITA PLUG & FLOAT EQUIPMENT

MANIFOLD	@		
	@		
	@		
	@		
	@		

TOTAL \_\_\_\_\_

TAX \_\_\_\_\_

TOTAL CHARGE ~~559.00~~

DISCOUNT ~~559.00~~ IF PAID IN 30 DAYS

SIGNATURE \_\_\_\_\_

*[Signature]*

ANY APPLICABLE TAX  
WILL BE CHARGED  
UPON INVOICING

PRINTED NAME \_\_\_\_\_

# ALLIED CEMENTING CO., INC. 14923

Federal Tax I.D.# ~~14-0707000~~

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
Great Bend

2nd Well

DATE <u>3-19-04</u>	SEC. <u>14</u>	TWP. <u>20</u>	RANGE <u>22w</u>	CALLED OUT <u>8:00 am</u>	ON LOCATION <u>3:00 pm</u>	JOB START <u>3:00 pm</u>	JOB FINISH <u>2:00 pm</u>
LEASE <u>Maier</u>	WELL # <u>#3</u>	LOCATION <u>Bazine - 11 south - 1/2 west</u>			COUNTY <u>Leas</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)			<u>South into</u>				

CONTRACTOR Plains  
 TYPE OF JOB Old Hole plug  
 HOLE SIZE T.D.  
 CASING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_  
 PRES. MAX 2000 MINIMUM \_\_\_\_\_  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_  
 CEMENT LEFT IN CSG. \_\_\_\_\_  
 PERFS. \_\_\_\_\_  
 DISPLACEMENT \_\_\_\_\_

OWNER RPSI

CEMENT  
 AMOUNT ORDERED 250 sy 20/40 6% gel with 30 gel + 200 hulls on side  
USED 45% CEMENT 1 1/2 GAL 200#

COMMON	<u>21 1/4</u>	@	<u>7.15</u>	<u>193.05</u>
POZMIX	<u>18 1/4</u>	@	<u>3.80</u>	<u>68.40</u>
GEL	<u>14</u>	@	<u>10.00</u>	<u>140.00</u>
CHLORIDE		@		
<u>HULLS 200#</u>		@	<u>18.00</u>	<u>36.00</u>
		@		
		@		
		@		
		@		
HANDLING	<u>293 1/4</u>	@	<u>1.15</u>	<u>336.96</u>
MILEAGE	<u>293 1/4</u>	@	<u>24</u>	<u>331.60</u>
				TOTAL <u>1126.00</u>

**EQUIPMENT**

PUMP TRUCK CEMENTER Tack  
 # 120 HELPER J.D.  
 BULK TRUCK  
 # 344 DRIVER Steve  
 BULK TRUCK  
 # \_\_\_\_\_ DRIVER \_\_\_\_\_

**REMARKS:**

Bullhead 5 1/2 agg mixed 30 sy cement with 200 lbs of hulls mixed in followed with 1 1/2 sy gel mixed with 21 1/2 gal of water - pressured to 2000 lbs - Released to get unit over hole - Pumped 15 1/4 HULLS PRESS SORT  
Thanks

**SERVICE**

DEPTH OF JOB 2nd Well  
 PUMP TRUCK CHARGE \_\_\_\_\_ 225.00  
 EXTRA FOOTAGE \_\_\_\_\_ @ \_\_\_\_\_  
 MILEAGE 24 @ 3.50 NC  
 PLUG \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_

RECEIVED

TOTAL 225.00

CHARGE TO: Falcon Exploration  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

KCC WICHITA FLOAT EQUIPMENT

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_  
 TOTAL CHARGE \_\_\_\_\_  
 DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE [Signature]

PRINTED NAME \_\_\_\_\_