

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED

MAY 03 2004

KCC WICHITA

Form CP-4

December 2003

Type or Print on this Form

Form must be Signed

All blanks must be Filled

Lease Operator: GERHARD E ONNEN

Address: 862 50th Rd Yates Center KS 66783

Phone: (620) 625-3396 Operator License #: 9672

Type of Well: Oil Docket #: 15-207-22,283
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 3/21/04 (Date)

by: Clayton Tittel (KCC District Agent's Name)

Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☒ No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: Bottom: T.D. 1147

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number: 15-207-22,283-00-00

Lease Name: ONNEN

Well Number: 21 SW SE SE

Spot Location (QQQQ): SE SW SE 1/4

165 Feet from ☐ North / ☒ South Section Line

1160 Feet from ☒ East / ☐ West Section Line

Sec. 12 Twp. 26 S. R. 14 ☒ East ☐ West

County: Woodson

Date Well Completed: 3/23/04 4:30 PM

Plugging Commenced: 3/23/04 9:00 AM

Plugging Completed: 3/23/04 4:30 PM

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
<u>Surf</u>		<u>40'</u>	<u>0'</u>	<u>7"</u>	<u>40</u>	<u>0</u>
<u>Prod</u>		<u>1147'</u>	<u>0'</u>	<u>2 3/8"</u>	<u>1147</u>	<u>0</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1" pipe was run into the 2 3/8" casing to 1125'. Cement was pumped into the 1" pipe until cement circulated from the 2 3/8" casing at surface. The 1" pipe was removed. Displacement was filled from surface. 35 sacks of cement were pumped into this well.

Name of Plugging Contractor: F & S Oil License #: RECEIVED 4845

Address: 1322 Apache Rd Virgil KS 66870 KCC District #3


Name of Party Responsible for Plugging Fees: Herbert L Fife

State of KS County, Woodson, ss. APR 29 2004

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Herbert L Fife

(Address) 1322 Apache Rd Virgil KS 66870



SUBSCRIBED and SWORN TO before me this 28th day of April, 2004

Jamie S Matile My Commission Expires: 11-15-04
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

3 022549

Duplicate

(To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 9672Operator: GERHARD E. ONNENName & 862 50TH. ROADAddress YATES CENTER, KS. 66783AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

Other well as hereinafter indicated: _____

Plugging Contractor: F & S OILLic. # 4845Address: 1322 APACHE ROAD, VIRGIL, KANSAS 66870Company to plug at: Hour: 9:00A.M. Day: 23 Month: 3 2004Plugging proposal received from: HERB FIFECompany Name: W & W PRODUCTION COMPANY Phone: 620-431-4137Were: THIS WELL CONSISTED OF 2 7/8" CASING TO 1147' THAT HAD BEEN CEMENTEDIN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 2 7/8"CASING FULL OF CEMENT

Plugging Proposal Received by:

CLAYTON P. TITELPlugging attended by Agent: All ☐ Part ☐

TECHNICIAN

None ☒Operations Completed: Hour: 4:30P.M. Day: 23 Month: 3 2004Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2 7/8" CASING TO 1125'.CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE2 7/8" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLEDFROM SURFACE. 35 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.**RECEIVED**

KCC

District #3


APR 29 2004

Remarks:

(If additional description is necessary, use BACK of this form.)I DID NOT observe this plugging.

Signed:

Chanute, KSClayton P. Titel
TECHNICIAN



VICTOR J. LEIS DRILLING COMPANY

Drilling Contractor

Box 223 Yates Center, KS 66783

316-625-2649

9672

API #

Well No. 1 Farm Onnen Producer Ned Primmer Oil Co.
Location Sec. Twp. Rg.
Elevation State KS County Woodson
Kind (Oil, Gas, Water, Dry Hole) oil Contractor Victor J. Leis Drilling Co.
Producing Formation Top Bottom
Shot With Qts. From To
Packer Set At Kind Size
Liner from to Perforated from to

LOG

Thickness	Strata	Depth	Thickness	Strata	Depth
	Top Soil	2		Shale	1065
	Clay	5 1/2		Sand-oil	1069
	Lime	11		Shale	1121
	Shale	15		Lime-ardmore	1122
	Sand(fresh water)	45		Shale	1235
	Shale	196		Black shale	1240
	Lime	205		Shale	1282
	Shale	210		Sand	1303
	Lime	226		Shale	1325
	Sandy Lime	252		T.D.	
	Lime	386			
	Shale(broken)	399			
	Lime	415			
	Sand-broken lime	450			
	Lime	466			
	Shale	497			
	Lime	502			
	Shale-red bed	513			
	Shale-gray	540			
	Lime	622			
	Shale-broken	640			
	Lime-B-KC	694			
	Shale	825			
	Lime-broken	841			
	Shale	856			
	Lime-broken	867			
	Shale-broken	904			
	Lime-sandy	932			
	Shale	953			
	Lime-broken	982			
	Shale-black	1060			

Total Depth

Open Hole

Casing at

Casing at

Casing at

Cement

Tubing

Rods

Additional Information Set 81' of 7" surface
pipe cemented with 20 sacks.

RECEIVED

KCC

District #3

APR 29 2004

Chanute, KS

Claton Tipton
Steve Korf

2 1/2 Casing

plugged 3-04

Date Completed

8-7-80

O.K.