

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-97523

A/P/E

15-129-10238-00-00

LEASE NAME Brown F

RECEIVED

TYPE OR PRINT

WELL NUMBER 1

MAY 03 2004

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3960 Ft. from S Section Line

3960 Ft. from E Section Line

KCC WICHITA

LEASE OPERATOR Oxy USA, Inc

SEC. 25 TWP. 34 RGE. 42 or (W)

ADDRESS 1701 N. Kansas PO Box 2528 Liberal, KS 67905

COUNTY Morton 3-17-57

PHONE(S) (620) 629-4200 OPERATORS LICENSE NO. 5447

Date Well Completed 2-6-59

Character of Well Gas

Plugging Commenced 4-5-04

(Oil Gas D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-2-04

The plugging proposal was approved on 4-13-04 (date)

by Jim Holland (KCC District Agent's Name)

Is ACO-1 filed? No If not, is well log attached? No ACO-1's not in use in 1957

Producing Formation Chase Depth to Top 3012 Bottom 3135 T.O. 3210

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Surf</u>			<u>601</u>	<u>8 5/8</u>	<u>601</u>	<u>A</u>
<u>Prod</u>			<u>3198</u>	<u>5 1/2</u>	<u>3198</u>	<u>830</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other products were used, state the character of same and depth placed, from feet to feet each
CIBP @ 2918 Load hole w/mud to 1300. Mixed 25 sx plug in 5 1/2 from 1300 to 1100 Mud to 0. Cut & pulled 5 1/2 to 600. Circ Hole w/mud 40 sx plug 600 to 480 30 sx 300 to 200 10 sx 40 to 0 Cut off & capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA, Inc. PO Box 2528 Liberal, KS 67905


STATE OF Kansas COUNTY OF Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed the same are true and correct, so help me God.

(Signature) Kenny Andrews

(Address) PO Box 2528 Liberal, KS 67905

SUBSCRIBED AND SWORN TO before me this 30th day of April, 19 2004



Kathleen R. Poulton
Notary Public

My Commission Expires: November 9, 2006