

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-22502-00-00  
Spot: NWSENE Sec/Twnshp/Rge: 29-8S-24W  
3464 feet from S Section Line, 825 feet from E Section Line  
Lease Name: KEITH Well #: 2  
County: GRAHAM Total Vertical Depth: 4000 feet

Operator License No.: 31933  
Op Name: M E KLEIN & ASSOCIATES, INC  
Address: PO BOX 721436  
NORMAN, OK 73070

CIBP Size: feet: 3550  
PROD Size: 4.5 feet: 4000 600 SX CMT  
SURF Size: feet: 0  
SURF Size: 8.625 feet: 225 250 SX CMT

\$130<sup>00</sup>

Well Type: EOR UIC Docket No: E25618.1 Date/Time to Plug: 05/04/2004 1:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: CARL ZIMMERMAN Company: M.E. KLEIN & ASSOCIATES, INC. Phone: (785) 625-1102

Proposed Plugging Method: Ordered out 150 sxs 60/40 pozmix - 10% gel - 16 sxs gel spacer.  
PBSD 3976'. Set CIBP at 3550'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/04/2004 7:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Set CIBP at 3550'.  
Ran tubing to 3542'.  
Allied pumped 16 sxs gel spacer with 200# hulls, followed with 20 sxs 60/40 pozmix - 10% gel.  
Pulled tubing to 1275'.  
Allied pumped 60 sxs 60/40 pozmix - 10% gel - cement circulated:  
PTOH. Squeezed with 10 sxs cement.  
Max. P.S.I. 500#. S.I.P. 500#.  
Hooked up to backside.  
Allied pumped 10 sxs cement.  
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3780	3790		

RECEIVED  
MAY 07 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE 5-7-04

INV. NO. 2004061537

MAY 05 2004

