

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-19163-00-00  
Spot: S2NENW Sec/Twnshp/Rge: 31-14S-14W  
3960 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: REXROAT Well #: 1  
County: RUSSELL Total Vertical Depth: 615 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

SURF Size: 8.625 feet: 560

6 35<sup>00</sup>

Well Type: SWD UIC Docket No: D02617.0 Date/Time to Plug: 04/23/2004 9:30 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: BOB GRANT Company: BEREXCO, INC. Phone: (316) 265-3311

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/23/2004 10:30 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

This well was left abandoned in 1965. It was a shallow SWD.  
Moved rig over hole and tried to washover 2 7/8" tubing.  
Drilled two feet of cement on outside of 2 7/8".  
Worked rod down to 45 feet inside of 2 7/8"  
Swedged in 8 5/8" over 2 7/8".  
Pumped on it with water and started taking fluid at 300# P.S.I.  
Pumped 100 sxs 60/40 pozmix 10% gel cement.  
Max. P.S.I. 450#. S.I.P. 300#.

RECEIVED  
MAY 07 2004  
KCC WICHITA

RECEIVED  
MAY 03 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

*Case Morris*

(TECHNICIAN)

INVOICED

DATE

5-7-04

AMOUNT

2004061538

APR 30 2004