

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22464-00-00
Spot: S2SWNWNW Sec/Twnshp/Rge: 26-31S-38W
1100 feet from N Section Line, 330 feet from W Section Line
Lease Name: SCHOWALTER A Well #: 3
County: STEVENS Total Vertical Depth: 6200 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: 1201 LAKE ROBBINS DRIVE
THE WOODLANDS, TX 77380

PROD Size: 5.5 feet: 4911 WITH 125 SX CMT
SURF Size: 8.625 feet: 1770 WITH 545 SX CMT

\$ 201⁵⁰

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/05/2004 9:00 AM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE
Proposal Rcvd. from: RICKY ESCEBEDO Company: EAGLE WELL SERVICE Phone: (620) 624-1904

Proposed Plugging Method: TOW SX HULLS AND 20 SX CLASS A CEMENT FROM 4749'-4642'. CUT OFF 5-1/2" CASING AT ABOUT 4200'. SET CLASS A CEMENT PLUGS AT 1820' TO 1651' WITH 50 SX CMT, 700' TO 568' WITH 40 SX CMT, AND 40' TO 4 WITH 10 SX CMT'. CUT OFF CASING AT 4' BELOW GL AND CAP WILL WITH STEEL CAP. AS PER KCC RULES & REGULATIONS.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/05/2004 2:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 4842'. PUMP 200# HULLS & 20 SX CMT. DISPLACE TO BOTTOM WITH 110 BBL MUD. PRESSURE TO 500 SPIG & SHUT IN. 1ST PLUG PULL OUT OF HOLE TO 1800'. CIRUCLATE HOLE WITH MUD & PUMP 50 SX CMT. DISPLACE WITH 35 BBL MUD. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 600'. LOAD HOLE & PUMP 40 SX CMT. DISPLACE WITH 12 BBL MUD. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 15 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4742	4749		

RECEIVED
MAY 11 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY EAGLE WELL SERVICE. RECOVERED 2500' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
MAY - 6 2004
KCC Dodge City

Signed

Jim Holland DIRTH
(TECHNICIAN)

INVOICED
DATE 5-11-04
INV. NO. 2004061546

Form CSG