

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21052-00-00
Spot: E2SENESW Sec/Twnshp/Rge: 31-32S-33W
1650 feet from S Section Line, 2610 feet from W Section Line
Lease Name: KAPP Well #: 1-31
County: SEWARD Total Vertical Depth: 6500 feet

Operator License No.: 32465
Op Name: BECK RESOURCES INCORPORATED
Address: P O BOX 175
HENNESSEY, OK 73742

PROD Size: 4.5 feet: 5878 WITH 300 SX CMT
SURF Size: 8.625 feet: 1564 WITH 615 SX CMT

\$211²⁵

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/27/2004 9:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PER KCC RULES & REGULATIONS. 20 SX CMT, 2 S HULLS TO 5500', 50 SX CMT 1580', 40 SX CMT/ @ 600', 10 SX 40' -0'.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/27/2004 3:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMP 100# HULLS & 20 SX CMT. DISPLACE TO BOTTOM WITH 85 BBL MUD. PRESSURE TO 500 PSIG & SHUT IN. 1ST PLUG CIRCULATE HOLE WITH MUD & PUMP 50 SX CMT AT 1585'. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 600'. CIRCULATE HOLE & PUMP 30 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. CIRCULATE HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
5616	5619		

RECEIVED
MAY 11 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1602' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland PART II
(TECHNICIAN)

INVOICED

DATE 5-11-04
INV. NO. 2004061547

Form CR 1/3
[Signature]