

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-20987-00-00  
Spot: NENWSE Sec/Twnshp/Rge: 5-30S-34W  
2070 feet from S Section Line, 1855 feet from E Section Line  
Lease Name: MLP ROONEY B Well #: 2-5  
County: HASKELL Total Vertical Depth: 5750 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: PO BOX 18496 6200 N WESTERN AVE.  
OKLAHOMA CITY, OK 73154

PROD Size: 4.5 feet: 5749 WITH 175 SX CMT  
SURF Size: 8.625 feet: 1745 WITH 675 SX CMT

88  
\$186

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/28/2004 2:00 PM

Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT. PLUG AT 1760' WITH 50 SX CMT. PLUG AT 660' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 04/30/2004 10:30 AM

KCC Agent: JIM HOLLAND

Actual Plugging Report:

Perfs:

04/28/04: PUMP 300# HULLS WITH 25 SX CMT. DISPLACE TO BOTTOM WITH MUD. 04/29/04: 1ST PLUG PULL OUT OF HOLE TO 1800'. CIRCULATE HOLE WITH MUD & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 650'. LOAD HOLE & PUMP 30 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. SDON. 04/30/04: LOAD HOLE & PUMP 10 SX CMT TO SURFACE.


Top	Bot	Thru	Comments
5596	5620		

RECEIVED  
MAY 11 2004  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1925' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland PIRELLI  
(TECHNICIAN)

INVOICED

DATE 5-11-04  
CCL NO. 2004061548

Form CP 23