

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-21467-00-00
Spot: E2NW Sec/Twnshp/Rge: 35-29S-34W
1410 feet from N Section Line, 2075 feet from W Section Line
Lease Name: MLP CLAWSON TRUST Well #: 5-35A
County: HASKELL Total Vertical Depth: 5577 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: PO BOX 18496 6200 N WESTERN AVE.
OKLAHOMA CITY, OK 73154

PROD Size: 5.5 feet: 5575 WITH 275 SX CMT
SURF Size: 8.625 feet: 1798 WITH 775 SX CMT

181²⁵

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/21/2004 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: MAX Company: ALLIED CEMENT COMPANY Phone: (785) 483-2627

Proposed
Plugging
Method:

PUMP 500# HULLS & 25 SX CMT. CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/21/2004 10:30 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 5532'. PUMP 500# HULLS & 25 SX CMT. PUMP 75 BBL SPACER TO 1800'.
PUMP 110 SX CMT FROM 1800' TO SURFACE. PRESSURE TO 750 PSIG & SHUT IN.
HOOK UP TO BACKSIDE. START CMT. PRESSURED TO 300 PSIG IMMEDIATELY.
BACKSIDE FULL.

Perfs:


Top	Bot	Thru	Comments
5420	5452		
5411	5418		

RECEIVED
MAY 11 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Jim Holland PIRETT
(TECHNICIAN)

INVOICED

DATE

5-11-04

INV. NO.

2004061548

Form CP-10