

6 031178

X 10-17 15-153-20059-00

API NUMBER 15- 1969

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW NW, SEC. 13, T. 1 S, R 34 W/E  
3300 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5552

Lease Name Ruda Well # 5 W

Operator: Gore Oil Co.

County Rawlins 139.10

Name & Address 125 N. Market Suite 1750

Well Total Depth 4280 feet

Wichita, Ks. 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 312

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well X SWD 5-20-04 D&A

Other well as hereinafter indicated E 18,265

Plugging Contractor Halliburton License Number \_\_\_\_\_

Address Oberlin, Ks. PM 17 Oct 88

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Lester Betts

(company name) Gore Oil (phone) \_\_\_\_\_

were: 8 5/8" set at 312' w/175 sks cwc. 5 1/2" set at 4279' w/1075 sks.

PB T.D. 4244'. Perf 4080' - 4220'. Order 250 sks 65/35 Poz 10% Gel

2% Diced. Halliburton Cement Co. Company water trucks. Pulled full string of RECEIVED hole open.

STATE CORPORATION COMMISSION  
12-29-88  
DEC 29 1988

Plugging Proposal Received by Carl Goodrow

(TECHNICIAN)  
CONSERVATION DIVISION  
WICHITA, KANSAS

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:15 PM Day: 17 Month: Oct Year: 19 88

ACTUAL PLUGGING REPORT Squeezed 5 1/2" w/200 sks cement blend, Backside communicated

Squeeze backside w/50 sks Cement Blend to max psi 250#. Close in 150#. Plug complete.

Remarks: \_\_\_\_\_

(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 1-5-89  
INV. NO. 23479

Signed Carl Goodrow  
Carl (TECHNICIAN)