

10-22-87 15-153-20173-00-00

6 030983

API NUMBER 15- 1974

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SW SW , SEC. 15 , T 1 S, R 34 W/E
660 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5988

Lease Name Cahoj Well # Supply Well

Operator: Halliburton Oil Prod. Co.
Name & Address: Box 10
Stafford, Kansas 67578

County Rawlins 91.03

Well Total Depth 2801 feet

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 304

Abandoned Oil Well ⁹¹⁵⁻²⁰⁻⁰⁴ Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: AM Day: 22 Month: Oct. Year: 19 87

Plugging proposal received from Mark

(company name) Kelso (phone)

were: 10 3/4" set at 304' w/225 sks cwc 7" set at 2800' w/400 sks. Perf 2286' - 2548'
Order sand and Common Cement. Shoot and pull pipe. Order 200 sks Econolite 65/35 Pozmix
10% Gel 2% Dixel Halliburton Cement Blend. LaRue Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 8:35 AM Day: 22 Month: Oct. Year: 19 87

ACTUAL PLUGGING REPORT Sand bottom to 2230' w/7 sks Common Cement on sand w/
bailer. Shots at 1500' - 800' 700- 600' 500' 400' . Recovered 400' of 7" casing.

Squeeze 10 3/4" and 7" w/75 sks cement blend w/5 sks Hulls mixed in. Circulated
cement on backside w/Max Psi 325#. Close ^{RECEIVED} STATE CORPORATION COMMISSION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

DATE 12-2-87

INV. NO. 19030

10-22 JAN 14 1988

cc. Bea Stong
Don Butcher

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow