

9-3-87 15-153-20103-00-00

6 030939

API NUMBER 15- 2-2-71

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NE SE, SEC. 15, T 1 S, R 34 (W) 4

1980 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5988

Lease Name Fikan Well # 2

Operator: Halliburton Oil Prod. Inc.

County Rawlins 140.79

Name & Address Box 10

Well Total Depth 4332 feet

Stafford, Kansas 67578

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 322

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: PM Day: 3 Month: Sept Year: 19 87

Plugging proposal received from Mark

(company name) Kelso (phone)

were: 8 5/8' set at 322' w/225 sks 5 1/2 set at 4331' w/200 sks. Perf 4158' - 4211'.

D. V. too 3034' w/500 sks. Order Common cement and sand. Pull pipe.

Order 200 sks Econolite 65/35 Pozmix 10% Gel 2% Dical Cement Blend, 5 sks Hulls.

Halliburton Services. LaRue Water Truck.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: Day: 3 Month: Sept Year: 19 87

ACTUAL PLUGGING REPORT Sand bottom to 4100' w/5 sks Common Cement on sand w/bailer.

6 shots at 1500' 1300' 1100' 900' 700' 600'.

Recovered 600' of 5 1/2 casing.

Squeezed down 8 5/8" casing w/5 sks Hulls in w/200 sks cement blend

Max Psi 500#. Close in 250# Psi. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form)

RECEIVED
STATE CORPORATION COMMISSION

SEP 25 1987

9-25-87
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
observe this plugging.

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow

DATE 9-28-87

INV. NO. 18285