

9-3-87

API NUMBER 15-193-20085-00-00

6 030938

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C NW SE, SEC. 15, T 1 S, R 34 W  
1980 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5988

Lease Name Fikan Well # 1  
County Rawlins

Operator: Halliburton Oil Prod. Co.  
Name & Address: Box 10  
Stafford, Kansas 67578

Well Total Depth 4339 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 311

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well X SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: \_\_\_\_\_ Day: 3 Month: Sept Year: 19 87

Plugging proposal received from Mark

(company name) Kelso (phone) \_\_\_\_\_

were: 8 5/8" set at 311' w/275 sks. 4 1/2" set at 4339' w/250 sks. PBTD 4319'.  
Perf. 4079' - 4261'. D.V. tool 3029' w/550 sks T.O.C. 1670'.

Order sand and Common Cement. Pull pipe. Order 200 sks Econolite 65/35 Pozmix  
10% Gel 2% Dical 5 sks Cmt. Blend. 5 sks Hulls.

Halliburton Services. LaRue Water Trucks.

Plugging Proposal Received by Carl Goodrow *Carl Goodrow*  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:20 AM Day: 3 Month: Sept Year: 19 87

ACTUAL PLUGGING REPORT Sand bottom to 4025' w/4 sks Common cement on sand with bailer.

Two shots at 1500' and 1400'. Recovered 1400' of 4 1/2" casing.

Squeezed down 8 5/8" casing w/5 sks Hulls in with 200 sks cement blend.

Max. Psi. 400# close in Psi 200#. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION  
9-25-87  
SEP 25 1987

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

**INVOICED**

Signed Carl Goodrow *Carl Goodrow*  
(TECHNICIAN)

DATE 9-29-87

Carl Goodrow

FORM CP-2/3 LR  
Rev. 01-84

INV. NO. 18289