

6 030942

9-3-87 15-153-20079-0000

API NUMBER 15- 7 - 2 - 70

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SE NW, SEC. 15, T 1 S, R 34 (W/W)
3300 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5988

Lease Name Dozhaba Well # A - 2

Operator: Halliburton Oil Prod Co.

County Rawlins 139.75

Name & Address Box 10

Well Total Depth 4300 feet

Stafford, Kansas 67578

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 372

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: AM Day: 3 Month: Sept Year: 19 87

Plugging proposal received from Mark

(company name) Kelso (phone)

were: 8 5/8" set at 372' w/250 sks. 5 1/2" set at 4299' w/300 sks. PBTB 4272'.
Perf. 4036' - 4215'. Order sand and Common Cement. Pull pipe.

Order 200 sks Econolite 65/35 Pozmix 10% Gel 2% Dical Cement Blend.

5 sks Hulls. Halliburton Services. LaRue Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:00AM Day: 3 Month: September Year: 19 87

ACTUAL PLUGGING REPORT Sand bottom to 3980' w/5 sks Common Cement on sand w/bailer.

Two shots at 2400' and 2000'. Recovered 2000' of 5 1/2" casing.

Squeezed 8 5/8" w/5 sks Hulls in with 200 sks cement blend.

Max. Psi 1000# close in Psi 150#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
9-25-87
SEP 25 1987

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Carl Goodrow (TECHNICIAN)

DATE 9-29-87

INV. NO. 18282