

9-3-87 15-153-20065-00-00

6 030941

API NUMBER 15-

12 - 13- 69

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

150' W
C NE SW, SEC. 15, T 1 S, R 34 W

1980 feet from S section line

3400 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5988

Lease Name Thieler Well # 4

Operator: Halliburton Oil Prod Co.

County Rawlins 141.31

Name & Address Box 10

Well Total Depth 4348 feet

Stafford, Kansas 67578

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 321

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: PM Day: 3rd Month: Sept. Year: 19 87

Plugging proposal received from Mark

(company name) Kelso (phone)

were: 8 5/8" set at 321' w/225 sks. 4 1/2" set at 4346' w/300 sks.

Perfs 4081' - 4256'. Order sand and Common Cement. Pull pipe.

Order 200 sks Econolite 65/35 Pozmix 10% Gel 2% Dicl. 5 sks Hulls.

Halliburton Services LaRue Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:50 PM Day: 3 Month: Sept Year: 19 87

ACTUAL PLUGGING REPORT Sand bottom to 4030' w/4 sks Common Cement on sand w/bailer.

4 shots at 2018' 1600' 1500' and 1400'.

Recovered 1400' of 4 1/2 casing.

Squeezed 8 5/8" casing w/5 sks Hulls in with 200 sks cement blend.

Max Psi 750#. Close in Psi 450#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 9-29-87

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 18288