

10-22-87 15-153-20004-00-00

To: 6 030985  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 1969  
SW NW, SEC. 15, T 1 S, R 34 (W/E)  
3300 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5988  
Operator: Halliburton Oil Prod. Co.  
Name & Address: Box 10  
Stafford, Ks. 67578

Lease Name Rosa Dozbaba Well # A-1  
County Rawlins 138.81  
Well Total Depth 4271 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 357

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address Chase, Ks.

Company to plug at: Hour: AM Day: 22 Month: Oct. Year: 19 87

Plugging proposal received from Mark  
(company name) Kelso Casing (phone) \_\_\_\_\_

were: 8 5/8" set at 357' w/275 sks cwc. 5 1/2 set at 4268' w/150 sks. Perf 4160'-4170'.

Order sand and Common Cement. Shoot and pull pipe. Order 200 sks Econolite  
65/35 Poz 10% Gel 2% Dical. Halliburton Cement Blend 5 sks Hulls. LaRue Water  
Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN) *Carl Goodrow*

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:00 AM Day: 22 Month: Oct. Year: 19 87

ACTUAL PLUGGING REPORT Sand bottom to 4110' w/5 sks Common Cement on sand w/bailer

shots at 2500' 2300' 2200' 2000' 1800'. Recovered 1800' of 5 1/2" casing.

Squeezed 8 5/8" w/200 sks Cement Blend w/5 sks Hulls mixed in to Max Psi

350#. Close in Psi 150#. Plug complete.

NOV 30 1987  
11-30-87  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

Signed Carl Goodrow (TECHNICIAN) *Carl Goodrow*  
Carl Goodrow

DATE 12-4-87  
INV. NO. 19109