

4-032087

9-6

00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-153-20,419

W2 NW NW /4 SEC. 13, 01S, 34 W
4620 feet from S section line
4950 feet from E section line

Operator license# 5552

Lease: Ruda Well # 7

Operator: Gore Oil Company

County: Rawlins

Address: P.O. Box 2747
Wichita, Kansas 67201

Well total depth 4325 140.56 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 297 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Halliburton License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 6 Month: September Year: 1995

Plugging proposal received from: Lester Betts

Company: Gore Oil Company Phone:

Were: Order 400 sxs 60/40 pozmix - 6% gel - 500# hulls.

RECEIVED
STATE CORPORATION COMMISSION

SEP 15 1995

CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by: Carl Goodrow 9-15-95

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 12:45 P.M., Day: 6, Month: September, Year: 1995

Actual plugging report: 8 5/8" set at 297' cwc with 300 sxs. 5 1/2" set at 4324' with 950 sxs. P.B.T.D. 4302'. 5 1/2" cemented from 4324' to surface with 950 sxs. Squeezed 5 1/2" with 350 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 0#. Close in P.S.I. 0#. 8 5/8" has cement to surface. Could not pump into. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO

Plugged through TUBING, CASING. Elevation: GL

did [X] / did not [] observe the plugging.

Carl Goodrow

(agent)

DATE OCT 04 1995

INV. NO. 43640

Form CP-2/3