

6 030932

9-27-87

API NUMBER 15- 153-20,219 -00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NW, SEC. 13, T 1 S, R 34 W

4620 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5552

Lease Name Ruda Well # 6

Operator: Gore Oil Company

County Rawlins 139.75

Name & Address 125 N. Market #1750

Well Total Depth 4300 feet

Wichita, Kansas 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 323

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address Oberlin, Kansas

Company to plug at: Hour: AM Day: 27 Month: August Year: 19 87

Plugging proposal received from Lester Betts

(company name) Gore Oil Co. (phone)

were: 8 5/8" set at 323 w/200 sks 5 1/2" set at 4299' w/350 sks. PBD 4270'.

Perf 4062' - 4245' CIBP at 4010'. DV tool at 3024 w/220 sks.

Order 225 sks 65/35 Pozmix 10% Gel 2% Dical Cmt Blend, 6 sks Hulls.

Halliburton Cmt. Co. water trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:30 AM Day: 27 Month: August Year: 19 87

ACTUAL PLUGGING REPORT Squeezed down 5 1/2" w/130 sks cmt blend w/5 sks Hulls mixed

in. Max Psi. 1000# close in 500# Psi.

Squeezed backside w/95 sks cmt blend w/1 sk Hulls mixed in.

Max Psi 400# close in 400# Psi. Plug complete.

RECEIVED STATE CORPORATION COMMISSION

SEP 25 1987

9-25-87

CONSERVATION DIVISION Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

INVOICED

Signed Carl Goodrow (TECHNICIAN)

DATE 9-28-87

INV. NO. 18284

Carl Goodrow