

KANSAS

*J*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20126-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 8 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
11-8-71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Halliburton Oil Producing Company,

Complete Address 117 Cameron Building, Oklahoma City, Oklahoma.

Lease Name Fikan Well No. 3

Location CSE-SE Sec. 15 Twp. 1 Rge. (E) (W) 34

County Rawlins Total Depth 4345'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas License No.     

Operation Completed: Hour 5:30 AM Day 3 Month 11 Year 1971

The above well was plugged as follows:

332'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1925'.

Circulated hole with heavy mud. Pulled DP to 2150' and displaced 100 Sx. cement thru  
DP from 2150' to 1825'. Pulled DP to 340' and displaced 25 Sx. cement thru DP from  
340' to 265'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *N. L. Dickels*  
Well Plugging Supervisor

DATE 11-11-71

INV. NO. 4644-111