

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-30066-00-00

RECEIVED
OCT 2 1966
10-2-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Empire Drilling Company.

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name Horinek Well No. B-2

Location CNW-SW Sec. 12 Twp. 1 Rge. (E) (W) 34

County Rawlins Total Depth 4275

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 5:45AM Day 29 Month 9 Year 1966

The Above well was plugged as follows:

259'--8 5/8" Surface pipe, cement circulated with 135 Sx.
Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.
cement thru DP. Heavy mud to 240', set plug with 1/4 sack hulls and dis-
placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack
hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 10/3/66
INV. NO. 4029-W