

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-153-20157-0000

RECEIVED
STATE CORPORATION COMMISSION

NOV 27 1974
11-27-74
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name Horinek Well No. 1

Location SE-SE Sec. 12 Twp. 1 Rge. (E) (W) 34

County Rawlins Total Depth 4275'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling,

Address P. O. Box #176, Chase, Kansas. License No. 683

Operation Completed: Hour 3:15 PM Day 22 Month 11 Year 1974

The above well was plugged as follows:

245'--8 5/8" Surface casing, cement circulated with 175 Sx.
4274'--4 1/2" Production casing cemented on bottom with 200 Sx. Well plugged back to
4238'. Top of perforations @ 4092'.

Pushed plug to 4000', sanded back to 3975' and set 3 Sx. cement with dump bailer.

Pulled 4 1/2" casing and squeezed well initially with 5 sacks hulls and 9 sacks gel foll-
owing with 110 Cu. Ft. cement from 2075' to 1750' then 37 sacks gel from 1750' to 270'
and followed with 30 Cu. Ft. cement from 270' to 200'. Then 4 sacks gel from 200' to
40' and finally 10 Cu. Ft. cement from 40' to bottom of cellar. Maximum pump-in press-
ure-300#. PSIP-150#. (Mudding and cementing by Allied Cementing Co., Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 12/2/74

INV. NO. 371-W