

KANSAS

70
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-153-20111-00-00

RECEIVED
STATE CORPORATION COMMISSION
APR 30 1971
CONSERVATION DIVISION
Wichita, Kansas
4-30-71

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center Building, Wichita, Kansas.

Lease Name Fikan Well No. 1

Location CSW-NE Sec. 15 Twp. 1 Rge. (E) (W) 34

County Rawlins Total Depth 4340

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 7:00 AM Day 26 Month 4 Year 1971

The above well was plugged as follows:

322'--8 5/8" Surface casing, cement circulated with 200 Sx.

Circulated hole with heavy mud. Pulled DP to 1750' and displaced 100 Sx. cement thru

DP from 1750' to 1425'. Pulled DP to 330' and displaced 25 Sx. cement thru DP from

330' to 255'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to

bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Nichols
Well Plugging Supervisor

DATE 4/30/71

INV. NO. 3629-11