

KANSAS

20

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-153-2088-00-00

10-14-70
RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Skelly Oil Company,

Complete Address 1860 Lincoln Street, Denver Colorado.

Lease Name Rosa Dozbaba Well No. A-3

Location 60' West of CNE-NW Sec. 15 Twp. 1 Rge. (E) (W) 34

County Rawlins Total Depth 4343'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Gabbert-Jones, Incorporated,

Address 830 Sutton Place, Wichita, Kansas. License No.

Operation Completed: Hour 4:30 PM Day 12 Month 10 Year 1970

The above well was plugged as follows:

370'--8 5/8" Surface casing, cement circulated with 275 Sx.
Top of Dakota section @ 1900'.

Circulated hole with heavy mud. Pulled DP to 2125' and displaced 100 Sx. cement thru
DP from 2125' to 1800'. Pulled DP to 390' and displaced 25 Sx. cement thru DP from
390' to 315'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICE

Signed: *W. L. Nichols*
Well Plugging Supervisor

DATE 10-14-70

INV. NO. 2680-W