

9

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-30068-0000

RECEIVED
STATE CORPORATION COMMISSION
OCT 20 1966
10-20-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Empire Drilling Company,

Complete Address: 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Horinek Well No. B-3

Location CSE-SW Sec. 12 Twp. 1 Rge. (E) (W) 34

County Rawlins Total Depth 4247

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 1:00PM Day 18 Month 10 Year 1966

The Above well was plugged as follows:

262'--8 5/8" Surface pipe, cement circulated with 125 Sx.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.

cement thru DP. Heavy mud to 250', set plug with 1/4 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Dinkel
Well Plugging Supervisor

DATE 10-20-66

INV. NO. 4139-W