



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

APR 13 1971

CONSERVATION DIVISION  
Wichita, Kansas

4-13-71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name: Morinek Well No. A-1

Location: CSW-NE Sec. 11 Twp. 1 Rge. (E)(W) 34

County: Rawlins Total Depth 4289' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Unruh was instructed to plug the well as follows:

195'--8 5/8" Surface casing, cement circulated with 100 Sx.  
4230'--4 1/2" Production casing cemented on bottom with 125 Sx. Well  
plugged back to 4176'. Top perforations @ 4098'.

Sand well back to 4075' and set 3 Sx. cement with dump bailer. Pull 4 1/2"  
casing and squeeze well with 5 sacks hulls, 50 sacks gel and 150 Sx.  
cement, staged.

Very truly yours,

Conservation Division Agent