



15-153-20115-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 20 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
5-20-71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Art Hunt of Rains & Williamson Oil Co., has this date requested permission to plug the following described well:

Mr. Hunt guarantees payment of the plugging fee.

Operator's full Name: George A. Reed,

Complete Address: 1223 Union National Building, Wichita, Kansas.

Lease Name: Kisling Well No. 1

Location: CNE-SW Sec. 10 Twp. 1 Rge. (E)(W) 34

County: Rawlins Total Depth 4295' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Hunt was instructed to plug the well as follows:

321'--8 5/8" Surface casing, cement circulated.  
Top of Dakota section @ 1775'.

Circulate hole with heavy mud. Pull DP to 2000' and displace 100 Sx. cement thru DP. Pull DP to 330' and displace 30 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

A. L. Nichols  
Conservation Division Agent