

KANSAS

Form CP-3
Rev. 6-4-68

R

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-153-30064-00-00

RECEIVED
STATE CORPORATION COMMISSION
APR 13 1971
CONSERVATION DIVISION
Wichita, Kansas
4-13-71

Operator's Full Name Empire Drilling Company,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Morinek Well No. A-1

Location CSW-NE Sec. 11 Twp. 1 Rge. (E) (W) 34

County Rawlins Total Depth 4289'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 4:00 PM Day 8 Month 4 Year 1971

The above well was plugged as follows:

195'--8 5/8" Surface casing, cement circulated with 100 Sx.

4230'--4 1/2" Production casing cemented on bottom with 125 Sx. Well plugged back to 4176'. Top perforations @ 4098'.

Sanded well back to 4075' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing (2010') and squeezed well initially with 5 sacks hulls and 8 sacks gel and followed with 115 Sx. cement from 2100' to 1775' then 39 sacks gel from 1775' to 225' and followed with 25 Sx. cement from 225' to 150' then 3 sacks gel from 150' to 30' and finally 10 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure--300#. Final shut-in pressure-150#. (Mudding and cementing operations by Halliburton).

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 4/13/71
INV. NO. 3538-W