

KANSAS

*20*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20115-06-00

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 20 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
5-20-71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name George A. Reed,

Complete Address 1223 Union National Bank Building, Wichita, Kansas.

Lease Name Kisling Well No. 1

Location CNE-SW Sec. 10 Twp. 1 Rge. (E) (W) 34

County Rawlins Total Depth 4295'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Rains & Williamson Oil Company, Incorporated,

Address 1425 Wichita Plaza, Wichita, Kansas. License No.       

Operation Completed: Hour 4:45 AM Day 15 Month 5 Year 1971

The above well was plugged as follows:

321'--8 5/8" Surface casing, cement circulated.  
Top of Dakota section @ 1775'.

Circulated hole with heavy mud. Pulled DP to 2000' and displaced 100 Sx. cement thru  
DP from 2000' to 1675'. Pulled DP to 330' and displaced 30 Sx. cement thru DP from  
330' to 240'/ Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5-20-71

INV. NO. 3727-W

Signed: *M. L. Nichols*  
Well Plugging Supervisor