

KANSAS

*Y*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-153-20102-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 15 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
12-15-70

Operator's Full Name Aspen Resources, Limited,

Complete Address 710 One-Twenty Building, Wichita, Kansas.

Lease Name Kisling Well No. 2

Location CSW-NE Sec. 10 Twp. 1 Rge. (E) (W) 34

County Rawlins Total Depth 4330'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Aspen Drilling Company,

Address Box #783, Great Bend, Kansas . License No. \_\_\_\_\_

Operation Completed: Hour 3:00 AM Day 9 Month 12 Year 1970

The above well was plugged as follows:

370'--8 5/8" Surface casing, cement circulated with 250 Sx.  
Top of Dakota section @ 1700'.

Circulated hole with heavy mud. Pulled DP to 1925' and displaced 100 Sx. cement thru  
DP from 1925' to 1600'. Pulled DP to 400' and displaced 25 Sx. cement thru DP from  
400' to 325'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Nichols*  
Well Plugging Supervisor

DATE 12/15/70  
INV. NO. 3061-u