

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-153-20157-00-00

RECEIVED  
STATE CORPORATION COMMISSIONNOV 27 1974  
11-27-74  
CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Darrell Kelso of Kelso Casing Pulling has this

date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.Operator's full Name: Chief Drilling Company, Incorporated,Complete Address: 905 Century Plaza, Wichita, Kansas.Lease Name: Horinek Well No. 1Location: SE-SE Sec. 12 Twp. 1 Rge. (E)(W) 34County: Rawlins Total Depth 4275' Oil Well XGas Well      Input Well      SWD Well      D & A      Lost Hole     Mr. Kelso was instructed to plug the well as follows:245'--8 5/8" Surface casing, cement circulated with 175 Sx.  
4274'--4 1/2" Production casing cemented on bottom with. Well plugged back  
to 4238'. Top of perforations @ 4092'.Push plug to 4000', sand to 3975' and set 3 Sx. cement with dump bailer.  
Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 50 sacks gel and  
150 Cu. Ft. cement, staged.

Very truly yours,

  
M. L. Nichols  
 Conservation Division Agent